



त्रिभुवन विश्वविद्यालय

शिक्षण अस्पताल

तार-दुयमेड
महाराजगञ्ज
काठमाडौं, नेपाल ।



पत्र संख्या :-

मिति : २०८१/१२/१७

यस त्रि.वि.शिक्षण अस्पतालको विभिन्न स्थानमा रहेको Toilet हरूमा Air exhaust Ventilation System जडान गर्न आवश्यक देखिएकोले उक्त System जडानको लागि आवश्यक यसै साथ संलग्न लिष्टमा भएका BOQ (Bill of quantity) तथा Technical Specification हरूको प्रचलित बजार मूल्यको आधारमा दररेट उपलब्ध गराईदिनु हुन अनुरोध छ । उक्त कार्य गर्न इच्छुक सम्बन्धित विषयमा इजाजत प्राप्त आ.व.२०८१/०८२ को लागि अस्पतालमा सूचीकृत वा अन्य व्यक्ति, फर्म तथा सप्लायर्सहरुले फर्म दर्ता, VAT दर्ता र पछिल्लो आ.व.को कर चुक्ता गरेको प्रमाणपत्रको प्रतिलिपि सहित अस्पतालको Website र सूचना पाटीमा यो सूचना प्रकाशित भएको मितिले ३ (तिन) दिन भित्र सामान्य प्रशासन शाखा 'ख' तथा tuthgeneraladmin@iom.edu.np मा पेश गर्नु हुन सम्बन्धित सबैको लागि जानकारी गराइन्छ ।

शोभा घिमिरे

प्रमुख

सामान्य प्रशासन शाखा 'ख'

TU Teaching Hospital, Maharajgunj

Technical Specification & BOQ of Toilet & room air exhaust ventilation system

S/N	Description	Unit	Qty	Unit/Rate	Amount in word	Total Amount
1	ICU-A Waiting Area Male/Female Toilet Exhaust					
1.1	Inline Fan - 240CFM	Nos.	1			
1.2	GI Ducting work	Sq.Ft.	1			
1.3	Aluminium Grille with Volume Control Damper(VCD) - 150x150mm	Nos.	1			
1.4	False ceiling work	Sq.Ft.	1			
1.5	Putting and paint work	Lot	1			
1.6	Automatic Electrical control waterproof box having 24Hr digital timer, MCB, contactor and complete wiring	Set	1			
2	Doctors Room air exhaust					
1.1	Rectangular type centrifugal Cabinet Fan - 1000CFM	Nos.	1			
1.2	GI Ducting work	Sq.Ft.	1			
1.3	Aluminium grille with Volume Control Damper(VCD) - 600x150mm	Nos.	1			
1.4	False ceiling work	Sq.Ft.	1			
1.5	Putting and paint work	Lot	1			
1.6	Automatic Electrical control waterproof box having 24Hr digital timer, MCB, contactor and complete wiring	Set	1			
3	Doctors Male/Female Toilet Exhaust					
1.1	Inline Fan - 415CFM	Nos.	1			
1.2	GI Ducting work	Sq.Ft.	1			
1.3	Aluminium grille with Volume Control Damper(VCD) - 150x150mm	Nos.	1			
1.4	False ceiling work	Sq.Ft.	1			
1.5	Putting and paint work	Lot	1			
1.6	Automatic Electrical control waterproof box having 24Hr digital timer, MCB, contactor and complete wiring	Set	1			
4	USG side Visitors Male/Female Toilet Exhaust					
1.1	Inline Fan - 415CFM	Nos.	1			
1.2	GI Ducting work	Sq.Ft.	1			



सिमुवन विद्यालय
सिमुवन विद्यालय
सिमुवन विद्यालय

Signature

1.3	Aluminium grille with Volume Control Damper(VCD) - 150x150mm	Nos.	1			
1.4	False ceiling work	Sq.Ft.	1			
1.5	Putting and paint work	Lot	1			
1.6	Automatic Electrical control waterproof box having 24Hr digital timer, MCB, contactor and complete wiring	Set	1			
5	Gyno OPD Ground Floor Side Male/Female Toilet Exhaust					
1.1	Rectangular type centrifugal Cabinet Fan - 1500CFM	Nos.	1			
1.2	GI Ducting work	Sq.Ft.	1			
1.3	aluminium grille with Volume Control Damper(VCD) - 150x150mm	Nos.	1			
1.4	False ceiling work	Sq.Ft.	1			
1.5	Automatic Electrical control waterproof box having 24Hr digital timer, MCB, contactor and complete wiring	Set	1			
6	ENT Ground Floor OPD Male/Female Toilet Exhaust					
1	Inline Fan - 415CFM	Nos.	1			
1.1	GI Ducting work	Sq.Ft.	1			
1.2	aluminium grille with Volume Control Damper(VCD) - 150x150mm	Nos.	1			
1.3	False ceiling work	Sq.Ft.	1			
1.4	False ceiling work	Sq.Ft.	1			
1.5	Putting and paint work	Lot	1			
1.6	Automatic Electrical control waterproof box having 24Hr digital timer, MCB, contactor and complete wiring	Set	1			

फर्मको नाम :

प्रोपाइटरको नाम :

हस्ताक्षर :

ठेगाना :

सम्पर्क नं.

मिति :

ईमेल :

छाप :

