



त्रिभुवन विश्वविद्यालय

# शिक्षण अस्पताल

तार-दुधमेड  
महाराजगञ्ज  
काठमाडौं, नेपाल ।

पत्र संख्या :-

मिति : .....



सूचना

२०८१।१२।३१

यस त्रि.वि.शिक्षण अस्पतालको ICU -B को लागी AC लगायतका विभिन्न सामानहरु खरिद तथा मर्मत गर्नु पर्ने भएकाले उक्त सामग्रीहरु आपूर्ति गर्न इच्छुक इजाजत प्राप्त सप्लायर्स/कम्पनी/फर्महरुले यो सूचना प्रकाशित भएको मितिले सात दिन भित्र आवश्यक सम्पूर्ण कागजात सहित शिलबन्दी दरभाउपत्र अस्पतालको सामान्य प्रशासन शाखा "क" मा पेश गर्नुहुन सूचित गरिन्छ । साथै थप जानकारीको लागी सामान्य प्रशासन शाखा 'क' मा सम्पर्क गर्न सकिनेछ ।

तपशिल :

SN	Description	QTY	Unit
1	Service charge for the installation of HEPA H14 Filter	16.00	nos
2	Installation of HEPA cabinet 300x 300 mm	16.00	nos
3	Fixing and maintenance of Duct with insulation and netting around the insulation of supply duct	1,000.00	sqft
4	Maintenance of Nursing counter with 1 mm Formica, Locks ,hinges etc around the damage area at tables all job complete	1.00	lot
5	PVC Conor guard 51mmX51mm width 90 degree	10.00	nos
6	Wall guard of PVC cover and aluminum wall Retainer with wooden color strip 197 mm height and 5 m long all the necessary accessories included such as screw with allocator anchor , vinyl retainer support aluminum back frame etc all job complete	3.00	meter
7	Maintenance of AHU and Outdoor unit including cleaning, Leakage testing of copper pipes Filter and fittings etc	2.00	sets
8	Maintenance of bed side pendant and sifting of Medical gas ports	12.00	Lot
9	Shifting of existing UPVC partition and door and rearranging them with required additional accessories and all job complete	1.00	Lot
10	VINYL FLOORING Providing and laying of 2mm thick homogeneous Phthalate free, PVC Vinyl flooring with a single layer of PVC, total weight is 3000 g/m <sup>2</sup> , XR PUR (poly uratheane reinforced, Abrasion group T:<=2.0mm, residual indentation approx. 0.03mm, castor wheel test qualified.	27.88	SQM



त्रिभुवन विश्वविद्यालय


# शिक्षण अस्पताल


तार-दुधमेड  
महाराजगञ्ज  
काठमाडौं, नेपाल ।

पत्र संख्या :-

मिति : .....

SN	Description	QTY	Unit
11	Providing and applying two coats or more of readymade antibacterial paint with one coat of primer of NS approved color over all interior plastered/ wall putty surfaces of wall, column, beam and ceiling of buildings including cleaning and wetting the surface with cost of all materials and accessories, all complete as per specifications, drawings and instruction of engineer. (Asian paint/ Jenson and Nicolson or equivalent.)	139.50	SQM
12	Shifting of existing UPVC partition and door 60 X 60 mm with 5 mm glass and all required additional accessories and all job complete	3.16	SQM

  
.....  
सरस्वती गुरुङ्ग  
प्रमुख  
सामान्य प्रशासन 'क'

  
त्रिभुवन विश्वविद्यालय  
शिक्षण अस्पताल