



त्रिभुवन विश्वविद्यालय

शिक्षण अस्पताल

तार-दुधमेड
महाराजगञ्ज
काठमाडौं, नेपाल ।



पत्र संख्या :-

२०८२/०२/०५
मिति :

सूचना

यस त्रि.वि. शिक्षण अस्पतालको सुरेश वाग्ले भवनको भुईँ तल्लाको पूर्वतर्फ च्याम रहेको भागवाट ई.एन.टी. भवनको पश्चिमतर्फको भुईँ तलासँग जोडी विरामीहरु आवत जावत गर्न सजिलोको लागि जोड्ने (Bridging) कार्य गर्न आवश्यक भएको हुँदा उक्त कार्य गर्न सम्बन्धित विषयमा इजाजत पत्र प्राप्त आ.व. २०८१/८२ को लागि अस्पतालमा सूचीकृत वा अन्य व्यक्ति, फर्म तथा सप्लायर्सहरुले फर्म दर्ता, VAT दर्ता र पछिल्लो आ.व.को कर चुक्ता गरेको प्रमाणपत्रको प्रतिलिपि सहित अस्पतालको वेबसाइट र सूचना पाटीमा यो सूचना प्रकाशित भएको मितिले ७ (सात) दिनभित्र सिलबन्दी दरभाउपत्र सामान्य प्रशासन शाखा 'ख' मा पेश गर्नुहुन सम्बन्धित सबैको जानकारीको लागि यो सूचना प्रकाशित गरिएको छ । साथै Bill of Quantity (BOQ) यसैसाथ संलग्न गरिएको छ ।

शोभा घिमिरे

प्रमुख

सामान्य प्रशासन शाखा "ख"

त्रि.वि.शिक्षण अस्पताल, महाराजगञ्ज

Bridging सम्बन्धी कार्यको शिल्ड कोटेशन

Estimated BOQ:

S.N	Description of work	No	Unit	Quantity	Unit/Rate	Total Amount	Total Amount in Words
1.0	Site clearance (before & after) the construction work unwanted material like as dust, debris, etc far way from the hospital area.	1.0	L.S	1.00			
2.0	Dismantling & remove the wall & door and garbage in the hospital site. All work complete		cum	3.67			
3.0	Laying the brick wall 1:4 Cement & sand (Wages Of only labor, cement & sand).all work complete		cum	1.32			
4.0	12.5mm thick plaster		sqm	17.16			
5.0	supply , fabrication & fitting I-BEAM(125x70)mm & (100x50)mm I-beam & including necessary Material like plate , nutbolt. All work complete		KG.	134.35			
6.0	supply , fabrication & fitting Thickness 0.41mm Plain GI Sheet, .All work complete		sqm	4.26			
7.0	pcc(1:2:4)		cum	1.30			
8.0	Supply and laying Before approved the Brand tiles. Thickness 10-12mm Parking Tiles size (300x300)mm cement massonary(1:4) of cement & sand. After complete with putting of white cement. All work complete.		sqm	12.38			
9.0	supply & fitting Dia 50mm steel stainless hand rail & vertical post distance is 2m. Three row of horizontal Dia 25 steel stainless bar between surface & hand rail. All work complete		sqm	4.49			
10.0	supply , Laying & fitting 2mm thick Poly carbonet plain sheet including all necessary material as like hook , screw bolt. All work complete		sqm	20.00			

[Signature]



11.0	Supply, Fabrication & fitting 2mm thick 2 & 3 inch hollow square Pipe for horizontal & vertical post for bridge truss shade with primer & Enamel paint. all work complete	KG.	96.00			
	SUB TOTAL					
	VAT 13%					
	GRAND TOTAL					

फर्मको नाम:

प्रोप्राइटरको नाम थर:

ठेगाना:

मिति:

फोन / मोबाइल नं.:

स्ट्याम्प:

ईमेल:



Signature