



त्रिभुवन विश्वविद्यालय

शिक्षण अस्पताल

तार-दुधमेड
महाराजगञ्ज
काठमाडौं, नेपाल ।

पत्र संख्या :-



मिति :२०८२/०९/२३..

सूचना

यस त्रि.वि. शिक्षण अस्पतालको सर्जरी ओ.पि.डी. अगाडीको मंगालदेखि अर्थो ओ.पि.डी. पछाडीको गार्डेन हुदै ट्रेससेडको ढाँटनिरको भागमा Drain Line बनाउन अति आवश्यक भएको हुँदा तपसील वमोजिमको कार्य गर्न सम्बन्धित विषयमा इजाजत पत्र प्राप्त, आ.व. २०८१/८२ को लागि अस्पतालमा सूचीकृत व्यक्ति, फर्म तथा सप्लायर्सहरूले फर्म दर्ता, VAT दर्ता र पछिल्लो आ.व.को कर चुक्ता गरेको प्रमाणपत्रको प्रतिलिपि सहित अस्पतालको वेवसाइट र सूचना पाटीमा यो सूचना प्रकाशित भएको मितिले ३ (तिन) दिनभित्र सिलवन्दी दरभाउपत्र सामान्य प्रशासन शाखा 'ख' मा पेश गर्नुहुन सम्बन्धित सवैको जानकारीको लागि यो सूचना प्रकाशित गरिएको छ ।

शोभा घिमिरे

प्रमुख

सामान्य प्रशासन शाखा "ख"

त्रि.वि.शिक्षण अस्पताल, महाराजगञ्ज
Drain Line सम्बन्धी कार्यको शिल्ड कोटेशन

Estimated BOQ:

S.N.	Description of Work	Nos.	Unit	Quantity	Unit/Rate	Total Amount	Total Amount in Words
1.0	Site Clearance(Before & after construction) existing pipes & other unwanted material. completion the work faraway from the site.as per site engineer.		L.S	1.00			
2.0	Earth Excavation for Laying the sewer pipe & manhole.all type of soil including lead & lift up to5m as per instruction & direction all work complete.		Cum	62.20			
3.0	Dismantling & Existing cement concrete floor for Laying RCC hume pipe. All work complete.		Cum	1.71			
4.0	Laying stone solling after leveling with sand then laying hump pipe.all work complete		Cum	2.04			
5.0	Supply & laying Dia 300mm RCC hump pipe np2 with collars .all work complete as per site instruction		RM	45.20			
6.0	First class chimney madebrick masonry(1:4) For Manhole of specified size complete to level as per instruction & direction of Engineer.all work complete	1.0	cum	2.52			
7.0	Filling soil excavation of Earth surface without watering after laying the Pipe.all work complete as per site engineer		cum	48.58			



[Handwritten Signature]

8.0	Providing & fixing of square manhole cover medium approved size .all work complete.	2.0	Nos	2.0			
9.0	Providing & Laying 12.5mm thickcement &sand Plaster (1:4) inner side of the manhole includingcracking & wetting the surface & curing.all work complete.		sqm	10.96			
	SUB TOTAL						
	VAT 13%						
	GRAND TOTAL						

फर्मको नाम:

प्रोप्राइटरको नाम थर:

ठेगाना:

मिति:

फोन /मोबाइल नं.:

स्ट्याम्प:

ईमेल:



Handwritten signature